

# Singapore

## 5,000 sq. ft.

### GENERAL

- 5,000 sq. ft. raised floor within 210,000 sq. ft. data center
- High Performance Computing (HPC) capable, supports 150 wpsf
- Carrier-neutral facility
- 100% uptime service level agreement on power
- 24x7 staffed NOCC and remote hands support
- Dedicated cages and private suite options available

### POWER

- Multiple levels of redundancy available within same footprint (e.g. N, 2N)
- Scalable densities
- Diverse power delivered by two independent power grids
- 36 Generators

### COOLING

- 31.5-inch (800 mm) raised floor design
- Closed loop chilled water cooling design
- 31.65MW of total capacity with dual chilled water loops
- 5 Chilled Water Risers

### SECURITY

- Reinforced physical structure including concrete bollards, steel-lined walls for security, and bullet resistant glass
- Video surveillance and recording of the exterior and interior of each facility
- On-site security guards 24 hours a day, 365 days a year
- Man traps, revolving entrance doors; biometric and key card (color coded) security for rigid access control
- Cabinet and cage security options include individual locks and biometric scanners

### FIRE PROTECTION

- Very Early Smoke Detection Apparatus (VESDA) system; sampling air in parts per million coupled with a zonal dual-action interlocking dry-pipe system

### AMENITIES

- Underground entry points

